

CA751/2



Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION

Torque	0.8 Nm
Rated Current	76 A

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA751/2	Pre assembled Shorting Link for 2 way shorting.	50
CA751/3	Pre assembled Shorting Link for 3 way shorting.	50
CA751/4	Pre assembled Shorting Link for 4 way shorting.	50
CA751/10	Pre assembled Shorting Link for 10 way shorting.	10

SUITABLE FOR

CTS16U	16 sq.mm Standard Feed Through Terminal Blocks
CTS16	16 sq.mm Standard Feed Through Terminal Blocks