

CA725/2



**Pre Assembled Shorting Links**

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

**PRODUCT SPECIFICATION**

Torque	0.8 Nm
Rated Current	101 A

**ORDERING INFORMATION**

CAT. NO.	DESCRIPTION	STD. PACK
CA725/2	Pre assembled Shorting Link for 2 way shorting	50
CA725/3	Pre assembled Shorting Link for 3 way shorting	20
CA725/4	Pre assembled Shorting Link for 4 way shorting	20
CA725/10	Pre assembled Shorting Link for 10 way shorting	10

**SUITABLE FOR**

CTS25UN	25 sq.mm Standard Feed Through Terminal Blocks
CTS25UN	25 sq.mm Standard Feed Through Terminal Blocks